

FIDECS ENGINEERING PTE LTD

Company Registration No. 201220309H GST Registration No. 201220309H
39 Woodlands Close, #08-18 Mega@Woodlands, Singapore 737856
Tel: (65) 6555 1286
Email: enquiries@fidecsengineering.com

Ref. No.: FEPL/QT/2026/FEB/079/RG

27th February 2026

SF Tuas Pte Ltd

20 Tuas South Avenue 14,
#01-02/03 ESR Tuas Logistic Hub,
Singapore 637312

Attn: Mr. Rajeev Grag

Dear Sir,


RE: PROPOSED DEMOLITION AND FORWARD WORK AT 32 QUALITY ROAD

We refer to the above-mentioned subject.

We are pleased to submit our price proposal for the demolition and forward work, as attached, amounting to **S\$805,800.00 (Singapore Dollars: Eight Hundred Five Thousand And Eight Hundred Only)**.

Terms and Conditions: -

1. Scope of Work:
 - i) Demolition Work
 - a) BCA ST Approval and Demolition Permit
 - b) LTA Development and Building Control (DBC) for the adjacent Railway
 - c) Contractors' All Risks (CAR) and Public Liability Insurance
 - d) Precondition Survey
 - e) Pre-demolition Spot Level Survey
 - f) Piles Location Survey Plan
 - g) Post-demolition Spot Level Survey
 - h) Plugging of the last IC connection
 - i) Noise & Vibration Meter
 - j) Total structure demolition works – till the soffit of the pile cape
 - k) Removal of all demolished material
 - l) Backfilling & levelling of the demolished site, complete with a layer of hardcore
 - m) To carry out Trial Hole & submit Report to SLA
 - ii) Topographic Survey
 - iii) Cable Detection
 - iv) Soil Investigation Work
2. The Contract Period: 4 months from the date of obtaining the BCA Permit to Commence Demolition Work or LTA rail clearance whichever is later.



FIDECS ENGINEERING PTE LTD

Company Registration No. 201220309H GST Registration No. 201220309H

39 Woodlands Close, #08-18 Mega@Woodlands, Singapore 737856

Tel: (65) 6555 1286

Email: enquiries@fidecsengineering.com


Ref. No.: FEPL/QT/2026/FEB/079/RG

3. Cost Exclude:

- i) Service Diversion and Decommissioning of existing power supply and services.
- ii) Applications, liaison, and all fees related to termination, protection, and diversion of M&E services, whether temporary or permanent, if required.
- iii) Obtaining JTC Clearance & URA WP.
- iv) Asbestos survey, removal and disposal work, if any.
- v) Conduct Environmental Site Assessment (ESA).
- vi) Removal and disposal of any illegal dumping below ground level, if any.
- vii) Soil Treatment / Decontamination / Disposal works, if required.
- viii) Demolition of retaining wall/structure.
- ix) Any other works not mentioned above shall be excluded.

TERMS AND CONDITIONS

- 1) Validity of Quotation: 30 days from the date of issuance.
- 2) Payment Term:
 - a) 21 days upon issuance of Invoice.
 - b) 30% deposit, balance amount monthly progressive payment.
 - c) Full amount of quoted price shall be payable upon project completion without additional discounts or project retention sum.
 - d) Cheque shall be made payable to “**Fidecs Engineering Pte Ltd**”.
- 3) Job Confirmation: Minimum 7 working days advanced confirmation by Purchase Order or Returned Copy of this quotation with authorised signature and endorsed with Company Seal.
- 4) Cancellation:
 - a) All equipment and materials quoted prices shall be paid in FULL shall the Job confirmation be withdrawn at any time after issuance of job confirmation.
 - b) 30% of the total quoted prices less the payment as mentioned in para 4(a) will be charged if cancellation is made within 3 working days prior to agreed project/job commencement date.
- 5) Please note that we are a registered GST company and the above quotation does not include existing GST charges.



FIDECS ENGINEERING PTE LTD

Company Registration No. 201220309H GST Registration No. 201220309H

39 Woodlands Close, #08-18 Mega@Woodlands, Singapore 737856

Tel: (65) 6555 1286

Email: enquiries@fidecsengineering.com

Ref. No.: FEPL/QT/2026/FEB/079/RG

Shall you have any further inquiries, please do contact the undersigned at (HP) 9140 7769.

We look forward to receiving your job confirmation and serving you in the near future.

Thank you.

Yours faithfully

Renfred Goh (Mr)
Contract Manager
For and on behalf of
Fidecs Engineering Pte Ltd

Accepted By

Name/Signature/Company Stamp/

Date

Please refer to the following attachments for the breakdown cost of tender

S/No	Item	Unit	Qty	Rate	Amount
1a	Preliminary (ie, Site management, safety provision and etc)	sum	1.00	\$ 61,400.00	\$ 61,400.00
b	Temporary Hoarding and Washing Bay	sum	1.00	\$ 24,700.00	\$ 24,700.00
c	Earth Control Measures (ECM)	sum	1.00	\$ 20,000.00	\$ 20,000.00
d	Insurance(CAR and ER)	sum	1.00	\$ 11,200.00	\$ 11,200.00
2	<u>Demolition Work</u>				
a	Demolition Work	sum	1.00	\$ 626,600.00	\$ 626,600.00
b	Provision of Resident Technical Officer (RTO)	mth	4.00	\$ 6,500.00	\$ 26,000.00
3	<u>Forward Work</u>				
c	Topographic Survey	sum	1.00	\$ 8,300.00	\$ 8,300.00
	a Horizontal control in SVY21 system				
	b Vertical control in Singapore Height Datum. (TBM)				
	c Prepare pre-computation survey plan for Architect approval.				
	d Mark site Boundary points for hoarding works				
4	Cable Detection work	sum	1.00	\$ 1,800.00	\$ 1,800.00
5	Soil Investigation				
	Carry out soil investigation works to a maximum depth of 30m or				
a)	achieve 3 successive SPT N values of at least 100 blows per 300mm including the following items:-	borehole	6.00	\$ 3,300.00	\$ 19,800.00
	i. Mobilization and demobilization of rig to site				
	ii. Carrying out SPT sampling at 3m interval				
	iii. Carrying out 2 no of thin wall sampling (very soft to soft) or thick wall sampling (stiff)				
	iv. Conduct Lab tests (1 test per borehole):				
	- Carrying out moisture content				
	- Carry out Atterberg limit for 1 selected sample				
	- Carrying out Unconsolidated Undrained (UU) triaxial test for selected sample				
	- sieve analysis, hydrometer analysis				
	v. Backfilling and reinstatement of the borehole once terminated.				
	vi. Submission of final report includes PE endorsement, 2 hardcopies and AGS report				
b)	Extra over drilling in soil >30M includes SPT sampling	no	1.00	\$ 47.00	Rate Only
c)	Mazier sampling >2 NOS	no	1.00	\$ 117.00	Rate Only
d)	Hacking works on concrete/premix	Loc	1.00	\$ 293.00	Rate Only
e)	Extra rock coring >2M	m	1.00	\$ 210.00	Rate Only
f)	Conduct shear wave velocity includes pipes in existing BH to depth 30m	borehole	2.00	\$ 3,000.00	\$ 6,000.00
				Total Amount:	\$ 805,800.00